# GK & A Logistics Services Ltd - Port Terminal Presentation

## For: Nigerian Export-Import Bank (NEXIM)

**Date: October 3, 2025**

---

## Project Overview

GK & A Logistics Services Ltd presents our completed port terminal facility at the NPA Lighter Terminal, Ikorodu. This presentation showcases our infrastructure development and key facility details for your consideration.

---

## Terminal Facility Details

### Quay/Wharf Specifications

- **Quay Apron Area**: 37,305.84 $m^2$
- **Quay Length**: 1,232.2 m
- **Quay Width**: 28.38 m

These dimensions provide substantial capacity for maritime cargo handling operations and vessel berthing.

---

## Current Terminal Infrastructure

The images below show the current terminal facilities, demonstrating the operational capacity and infrastructure already in place.

*Figure 1: Overview of the current terminal facilities*

*Figure 2: Detailed view of terminal infrastructure*

*Figure 3: Terminal layout and operational areas*

*Figure 4: Completed perimeter security fence installation*

---

## Completed Security Infrastructure

As part of our commitment to providing a secure and compliant facility, we have completed the perimeter security fence installation around the terminal.

Figure 1: Terminal View 1

Figure 2: Terminal View 2

Figure 3: Terminal View 3

Figure 4: Wire Mesh Fence

### Fence Installation Details

- **Total Fence Length**: Approximately 784.85 m
- **Fence Height**: 2.44 m with three-strand barbed-wire topping
- **Posts**: 288 total posts (SHS 60x60x3.0 mm S355 line posts)
- **Mesh**: 50 mm aperture galvanized mesh, 3.55 mm wire thickness

---

## Gate System

The terminal features a comprehensive gate system for vehicle and pedestrian access control:

### Vehicular Gates

- **G1a & G1b**: Sliding gates, 5.72 m each (inbound/outbound)
- **G2**: Container gate, 12.19 m (sliding)
- **G3-G6**: Standard gates, 6.10 m each (sliding)

### Pedestrian Gates

- **P1**: Turnstile gate
- **P2**: Inter-terminal access gate
- **P3**: Emergency exit gate

---

## Technical Compliance

Our installation meets all required standards and regulations:

- **Nigerian Building Code** compliance
- **BS EN 1991-1-4**: Wind loading standards
- **BS EN 1993**: Steel structure design
- **BS EN 1992**: Concrete structure design
- **BS 1722**: Chain-link fencing standards
- **ISO 1461**: Hot-dip galvanizing specifications
- **ISO 12944**: Protective paint systems (Category C5-M marine exposure)

---

## Materials and Durability

### Structural Components

- **Steel Posts**: S355 grade steel (SHS 60x60x3.0 mm)
- **End/Corner Posts**: Upgraded SHS 80x80x4.0 mm sections
- **Mesh**: 50 mm aperture galvanized wire (3.55 mm thickness)

### Corrosion Protection

- **Duplex Coating System**: Hot-dip galvanizing plus epoxy/polyurethane topcoats
- **Total DFT**: 160-200 um for marine exposure (C5-M category)
- **Concrete**: C25/30 grade with XS3/XD3 exposure classes

---

## Quality Assurance

Our installation has undergone rigorous quality control processes:

- **Concrete Testing**: 7/28-day cube tests confirming C25/30 specification
- **Coating Inspection**: DFT measurements verifying coating thickness
- **Galvanizing Certification**: Thickness checks confirming ISO 1461 compliance
- **Bolt Torque Verification**: Torque checks on critical fixings
- **Anchor Testing**: Pull tests on foundation anchors where applicable

---

## Maintenance and Operations

We provide a comprehensive O&M plan for long-term facility sustainability:

- **Monthly Inspections**: Visual checks of mesh tension, fixings, and corrosion
- **Quarterly Maintenance**: Lubrication of sliding gate components
- **Six-Monthly Checks**: Torque verification of bolts and fixings
- **Annual Services**: Coating touch-ups and earthing system testing

---

## Project Documentation

The complete as-built submission package includes:

### Technical Drawings (11 sheets)

1. General Layout Plan and Key Plan (D-01)
2. Fence Elevations and Typical Bay (D-02)
3. Line Post and Mesh Fixing Details (D-03)
4. End/Corner/Strainer Post Details (D-04)
5. Gate GA and Foundations/Plinth Details (D-05)
6. Gate Hardware Details (D-06)
7. Foundation Schedules and Reinforcement (D-07)
8. Earthing and Bonding Details (D-08)
9. Notes and Schedules (Materials/Hardware) (D-09)

10. Typical Sections at Drainage/Crossings (D-10)
11. As-Built Survey Alignment and Coordinates (D-11)

**Supporting Documents (20 files)**

- Structural Design/Compliance Report
- QA/QC Logs (concrete, coatings, fixings)
- As-Built Survey Documentation
- O&M Plan and Warranty Letter
- Materials Certificate Schedule
- Site Acceptance Request

---

## Conclusion

GK & A Logistics Services Ltd has successfully completed a state-of-the-art port terminal facility that meets all international standards for maritime cargo handling. With our comprehensive security infrastructure, technical compliance, and commitment to quality, we are well-positioned to serve as a key logistics partner for Nigeria's export-import activities.

We welcome the opportunity to discuss how our facility can support NEXIM's initiatives in promoting Nigerian trade and economic development.

---

## Contact Information

**GK & A Logistics Services Ltd** - Managing Director: Omobola Abiru - Address: [Company Address] - Email: [Company Email] - Phone: [Company Phone]